



# जम्मू केंद्रीय विश्वविद्यालय Central University of Jammu

राया-सूचानी (बागला), जिला सांबा-181143, जम्मू (जम्मू एवं कश्मीर)  
Rahya-Suchani (Bagla), District: Samba - 181143, Jammu (J&K)

No: CUJ/W/2023/516

Date: 21.09.2023

.....  
.....  
.....

**Sub: - Quotation.**

**Name of Work: Providing & fixing gypsum false ceiling in Department of Chemistry.**

Dear Sir,

CUJ invites quotation for providing and Installation of False ceiling tiles in the Department of Chemistry. You are requested to quote the overall percentage for complete work: "At Par", or "Above" or "Below" in figures, as well as, in words (including GST) of the enclosed format. In case of any discrepancy noticed in the quoted percentage, the percentage quoted in words shall be considered. Electricity charges @ 1% shall be deducted in case the vendor uses the electricity from CUJ resources.

Terms and Conditions:-

1. The completion period is 7 days (Seven days) from the date of issue of work order.
2. The Estimated cost of work is Rs55500.00
3. Last date of submission of Quotation is 28/09/2023 at 12:00 hrs
4. Date of Opening of Quotation is 28/09/2022 at 15:00 hrs or as decided by Convenor LPC.
5. Validity of Quotation is 45 days from the date of opening of Quotation.
6. Bidders quoting percentage item wise shall be summarily rejected. Rates are inclusive of all taxes, loading Unloading, transportation Octroi, cess, GST etc. Rates are FOR at site.
7. Statutory deductions like TDS & Labour cess as per applicable rates will be made from the contractor's bill.
8. Rates quoted shall be firm and fix and no escalation shall be provided throughout the currency of the period of work.
9. No advance payment will be made.
10. GST Bill should be provided.

BK

# जम्मू केंद्रीय विश्वविद्यालय

## Central University of Jammu

राजा-सूचना (बागला), जिला सांबा-181143, जम्मू (जम्मू एवं कश्मीर)

Rahya-Suchani (Bagla), District: Samba - 181143, Jammu (J&K)

11. CUJ reserves the right to cancel the work before the commencement of work or at any stage of execution if found substandard or not as per required specifications.

12. Payment shall be made through RTGS/NEFT

13. Work is to be executed as per CPWD Specification 2019 VOL-1&VOL-2 with up-to-date

correction slip

14. If the bidder withdraws from the work after coming out as lowest within the bid validity period, the bidder shall be debarred from applying for further works in the University for period

of two year.

15. Bidders are required to submit following document along with Quotation:

i. Covering letter in Company letter head format.

ii. GST Registration/ Pan Card/Aadhar Card


iii. Contact Information of bidder (Complete address and Phone no.)

Encl: As Above

CC: Guard File  
Notice Board

Executive Engineer

(Er. Vishal Bagotra)

  
21/09/2023





# जम्मू केंद्रीय विश्वविद्यालय Central University of Jammu

राया-सूचानी (बागला), जिला सांबा-181143, जम्मू (जम्मू एवं कश्मीर)  
Rahya-Suchani (Bagla), District: Samba - 181143, Jammu (J&K)

Annexure-1

Sno	Description	Unit	Qty	Rate(Rs)	Amount(Rs)
1	Providing and fixing of gypsum False ceiling tiles in including the frame work of T-grid of at all heights of size 595X595mmX7mm thick of approved texture, design and pattern made of high quality paper-faced gypsum board with a PVC layer on the surface and aluminium foil (0.16mm) on the reverse The tiles should be made up of gypsum plaster board manufactured from natural gypsum. The tile fixing system includes Providing and fixing tiled false ceiling of specified materials of size595x595 mm in true horizontal level, suspended on inter locking metal grid of hot dipped galvanized steel sections consisting of main "T" runner with suitably spaced joints to get required length and of size 24x38mm spaced at 1200mm center to center and cross "T" of size 24x25 mm, 1200 mm long spaced between main"T" at 600 mm center to center to form a grid of 1200x600 mm and secondary cross "T" of length 600 mm and size 24x25 mm made interlocked at middle of the1200x600 mm panel to form grids of 600x600 mm and wall angle ofsize 24x24x0.3 mm and laying false ceiling tiles of approved texturein the grid including, required cutting/making, opening for services like diffusers, grills, light fittings, fixtures, smoke detectors etc. Main"T" runners to be suspended from ceiling using GI slotted cleats ofsize 27 x 37 x 25 x1.6 mm fixed to ceiling with 12.5 mm dia and 50mm long dash fasteners	sqft	740	75	55,500.00
	<b>Total</b>				<b>55500.00</b>

*BLT*  
*21/09/2023*



# Central University of Jammu

राजा-सूचना (बागला), जिला सांबा-181143, जम्मू (जम्मू एवं कश्मीर)  
Rahya-Suchani (Bagla), District: Samba - 181143, Jammu (J&K)

## Quotation Form

Name of Work: Providing & Fixing of False tiles Department of Chemistry of Central University of Jammu, Rahya Suchani, Bagla.  
Estimated Cost: Rs55500/-

Quote Percentage(Above/At Par/Below)	Estimated Cost (Inclusive of GST)	Rs.55500/-
In words	In figures	Providing & Fixing of False tiles Department of Chemistry of Central University of Jammu, Rahya Suchani, Bagla.

Signature & Stamp of the vendor