



जम्मू केंद्रीय विश्वविद्यालय
Central University of Jammu

राया-सूचानी (बागला), जिला सांबा-181143, जम्मू (जम्मू एवं कश्मीर)
Rahya-Suchani (Bagla), District: Samba - 181143, Jammu (J&K)

No: CUJ/W/2022/3307

Date: 23.05.2022

Sub: - Quotation.

Name of Work: Covering of Open area of Servant balcony of Servant Quarter no 25 in Central University of Jammu, Rahya Suchani Bagla Samba.

Dear Sir,

CUJ invites quotation for Covering of Open area of Servant balcony of Servant Quarter no 25 in Central University of Jammu, Rahya Suchani, Bagla. You are requested to quote the overall percentage for complete work: "At Par", or "Above" or "Below" in figures, as well as, in words (including GST) of the enclosed format. In case of any discrepancy noticed in the quoted percentage, the percentage quoted in words shall be considered. Electricity charges @ 1% shall be deducted in case the vendor uses the electricity from CUJ resources.

Terms and Conditions:-

1. The completion period is 14 days (Fourteen days) from the date of issue of work order.
2. The Estimated cost of work is Rs82232.00
3. Last date of submission of Quotation is 31/05/2022 at 12:00 hrs
4. Date of Opening of Quotation is 31/05/2022 at 15:00 hrs or as decided by Convenor LPC.
5. Validity of Quotation is 45 days from the date of opening of Quotation.
6. Bidders quoting percentage item wise shall be summarily rejected. Rates are inclusive of all taxes, loading Unloading, transportation Octroi, cess, GST etc. Rates are FOR at site.
7. Statutory deductions like TDS & Labour cess as per applicable rates will be made from the contractor's bill.
8. Rates quoted shall be firm and fix and no escalation shall be provided throughout the currency of the period of work.
9. No advance payment will be made.
10. GST Bill should be provided.
11. CUJ reserves the right to cancel the work before the commencement of work or at any stage of execution if found substandard or not as per required specifications.
12. Payment shall be made through RTGS/NEFT.




जम्मू केंद्रीय विश्वविद्यालय
Central University of Jammu

राया-सूचानी (बागला), जिला सांबा-181143, जम्मू (जम्मू एवं कश्मीर)
Rahya-Suchani (Bagla), District: Samba - 181143, Jammu (J&K)

- =====
13. Payment shall be made on the basis of actual measurement recorded at site.
 14. Work is to be executed as per CPWD Specification 2019 VOL-1&VOL-2 with up-to-date correction slip
 15. If the bidder withdraws from the work after coming out as Lowest within the bid validity period, the bidder shall be debarred from applying for further works in the University for period of two year.
 16. Bidders are required to submit following document along with Quotation:
 - i. Covering letter in Company letter head format.
 - ii. GST Registration/ Pan Card/Aadhar Card
 - iii. Contact Information of bidder (Complete address and Phone no.)

Encl: As Above


(Er. Vishal Bagotra)
Executive Engineer

CC: Guard File
Notice Board



जम्मु केंद्रीय विश्वविद्यालय
Central University of Jammu

राया-सूचानी (बागला), जिला सांबा-181143, जम्मू (जम्मू एवं कश्मीर)
Rahya-Suchani (Bagla), District: Samba - 181143, Jammu (J&K)

BOQ for Covering of open area of servant balcony of servant quarter 25					
S No	Description	Unit	Quantity	Rate(Rs)	Amount(Rs)
1	10.16 Steel work in built up tubular (round, Square or rectangular hollow tubes etc.) trusses etc, including cutting, hosting fixing in position and applying a priming coat of approval steel primer, including welding and bolted with special shaped washer etc. all complete. Rate to include all sunderies and scaffoldings	kg	110	154.9	17039
2	12.5 Providing and fixing at any height and level, precoated, coloured galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge) 0.50 mm (+ 0.05 %) total coated thickness with zinc coating 120 grams per sqm as per IS: 277, in 240 mpa steel grade, 5-7 microns epoxy primer on both side of the sheet and polyester top coat 15-18 microns. Sheet should have protective guard film of 25 microns minimum to avoid scratches during transportation and should be supplied in single length upto 12metre or as desired by Engineer-in-charge. The sheet shall be fixed using self drilling /self tapping screws of size (5.5x 55 mm) with EPDM seal, complete upto any pitch in horizontal/ vertical or curved surfaces, excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required. Rate to include all sunderies and scaffoldings.	sqm	12	671.55	8058.6
4	21.1.1.1 Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash	kg	50	433.95	21697.5



जम्मू केंद्रीय विश्वविद्यालय Central University of Jammu

राया-सूचानी (बागला), जिला सांबा-181143, जम्मू (जम्मू एवं कश्मीर)
Rahya-Suchani (Bagla), District: Samba - 181143, Jammu (J&K)

	fasteners to be paid for separately) :For fixed portion Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC 15)F				
5	12.53 Providing and Fixing 15 mm thick densified tegular edged eco friendly light weight calcium silicate false ceiling tiles of approved texture of size 595 x 595 mm in true horizontal level, suspended on inter locking metal grid of hot dipped galvanised steel sections (galvanising @ 120 grams per sqm including both side) consisting of main 'T' runner suitably spaced at joints to get required length and of size 24x38 mm made from 0.33 mm thick (minimum) sheet, spaced 1200 mm centre to centre, and cross "T" of size 24x28 mm made out of 0.33 mm (Minimum) sheet, 1200 mm long spaced between main'T' at 600 mm centre to centre to form a grid of 1200x600 mm and secondary cross 'T' of length 600 mm and size 24 x28 mm made of 0.33 mm thick (Minimum) sheet to be inter locked at middle of the 1200x 600 mm panel to form grid of size 600x600 mm, resting on periphery walls /partitions on a Perimeter wall angle pre-coated steel of size(24x24X3000 mm made of 0.40 mm thick (minimum) sheet with the help of rawl plugs at 450 mm centre to centre with 25 mm long dry wall screws @ 230 mm interval and laying 15 mm thick densified edges calicum silicate ceiling tiles of approved texture in the grid, including, cutting/ making opening for services like diffusers, grills, light fittings, fixtures, smoke detectors etc., wherever required. Main 'T' runners to be suspended from ceiling using G.I. slotted cleats of size 25x35x1.6 mm fixed to ceiling with 12.5 mm dia and 50 mm long dash fasteners, 4 mm G.I. adjustable rods with galvanised steel level clips of size 85 x 30 x 0.8 mm, spaced at 1200 mm centre to centre along main 'T', bottom exposed with 24 mm of all Tsections shall be pre-painted with polyster baked paint, for all heights, as per specifications, drawings and as directed by Engineer-in-Charge.	sqm	9.29	1688.8	15688.95

125



जम्मू केंद्रीय विश्वविद्यालय
Central University of Jammu

राया-सूचानी (बागला), जिला सांबा-181143, जम्मू (जम्मू एवं कश्मीर)
Rahya-Suchani (Bagla), District: Samba - 181143, Jammu (J&K)

5.1	21.1.2.1 Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately); For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (Fittings shall be paid for separately) : Anodised aluminium (anodised transparent or dyed to required shade according to IS: 1868, Minimum anodic coating of grade AC 15)	kg	17	531.48	9035.16
6	Providing and fixing Aluminium Composite panel 4.0 mm thick (Both side coloured) in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge excluding the cost of frame .	sqm	1	1386	1386
7	21.3.1 Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge . (Cost of aluminium snap beading shall be paid in basic item):	sqm	1	1019.8	1019.8
8	Providing and fixing aluminium handles, ISI marked, anodised or powder coated to required colour or shade, with necessary screws etc. complete: 125 mm	nos.	2	100	200
9	Providing and fixing aluminium sliding door bolts, ISI marked anodised (anodic coating not less than grade AC 10 as per IS: 1868), transparent or dyed	nos.	1	234.9	234.9

14



जम्मू केंद्रीय विश्वविद्यालय
Central University of Jammu

राया-सूचानी (बागला), जिला सांबा-181143, जम्मू (जम्मू एवं कश्मीर)
Rahya-Suchani (Bagla), District: Samba - 181143, Jammu (J&K)

	to required colour or shade, with nuts and screws etc complete				
	Repair of walls of open area of Servant Quarter 25				
10	CEMENT PLASTER (IN FINE SAND) 13.1 12 mm cement plaster of mix : 13.1.1 1:4 (1 cement: 4 fine sand)	sqm	10	294.85	2948.5
11	Finishing walls with textured exterior paint of required shade : 13.110.1 Old work (Two or more coats on existing cement paint surface applied @ 3.28 ltr/10 sqm.	sqm	10	191.4	1914
12	Applying priming coats with primer of approved brand and manufacture, having low VOC (Volatile Organic Compound) content. 13.85.3 with water thinnable cement primer on wall surface having VOC content less than 50 grams/litre	sqm	10	64.45	644.5
13	13.61 Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : 13.61.1 Two or more coats on new work	sqm	18	131.41	2365.38
	Total sum				82232.3
				Say Rs	82232

Rupees Eighty Two Thousand Two hundred and Thirty two.



जम्मू केंद्रीय विश्वविद्यालय
Central University of Jammu

राया-सूचानी (बागला), जिला सांबा-181143, जम्मू (जम्मू एवं कश्मीर)
Rahya-Suchani (Bagla), District: Samba - 181143, Jammu (J&K)

Quotation Form

Name of Work: BOQ for Covering of open area of servant balcony of servant quarter 25

Estimated Cost: Rs.82232 (Rupees Eighty Two Thousand Two hundred and Thirty two.)

Estimated Cost (Inclusive of GST)	Quote Percentage(Above/At Par/Below)	
	In figures	In words
Rs82232.00 (Rupees Eighty Two Thousand Two hundred and Thirty two.)		

BK

Signature & Stamp of the vendor

