



जम्मू केंद्राय विश्वाविद्यालय  
Central University of Jammu

राया-सूचानी (बागला), जिला सांबा-181143, जम्मू (जम्मू एवं कश्मीर)  
Rahya-Suchani (Bagla), District: Samba - 181143, Jammu (J&K)

No: CUJ/W/2022/2675

Date: 24.02.2022

Sub: - Quotation.

Name of Work: Construction of Sink and washbasin Platform at Central University of Jammu.

Dear Sir

The CUJ intends construct the sink and washbasin platform near canteen in Central University of Jammu and therefore, you are requested to quote the overall percentage for complete work: "At Par", or "Above" or "Below" in figures, as well as, in words (including GST) of the enclosed format. In case of any discrepancy noticed in the quoted percentage, the percentage quoted in words shall be considered. Electricity charges @ 1% shall be deducted in case the vendor uses the electricity from CUJ resources.

1. The completion period is 21 days (fourteen days) days from the date of issue of work order.
2. The Estimated cost of work is Rs63960.00(Inclusive of GST)
3. Last date of submission of Quotation is 07/03/2022 at 12:00 hrs
4. Date of Opening of Quotation is 07/03/2022 at 15:00 hrs
5. Validity of Quotation is 45 days from the date of opening of Quotation.
6. Bidders quoting percentage item wise shall be summarily rejected. Rates are inclusive of all taxes, loading Unloading, transportation Octroi, cess, GST etc. Rates are FOR at site.
7. Statutory deductions like TDS & Labour cess as per applicable rates will be made from the contractor's bill.
8. Rates quoted shall be firm and fix and no escalation shall be provided throughout the currency of the period of work.
9. No advance payment will be made.
10. GST Bill should be provided.
11. CUJ reserves the right to cancel the work before the commencement of work or at any stage of execution if found substandard or not as per required specifications.
12. Payment shall be made through RTGS/NEFT
13. Work is to be executed as per CPWD Specification 2019 VOL-1&VGL-2 with up-to-date correction slip
14. If the bidder withdraws from the work after coming out as Lowest within the bid validity period, the bidder shall be debarred from applying for further works in the University for period of two year.



जम्मू केंद्राय विरवावद्यालय  
**Central University of Jammu**

राया-सूचानी (बागला), जिला सांबा-181143, जम्मू (जम्मू एवं कश्मीर)  
**Rahya-Suchani (Bagla), District: Samba – 181143, Jammu (J&K)**

---

15. Liquidity damages @ 1% per week would be applied subjected to maximum ceiling of 10% of contract amount if the work is not completed on time.
16. Bidders are required to submit following document along with Quotation:
- Covering letter in Company letter head format.
  - GST Registration/ Pan Card/Aadhar Card
  - Contact Information of bidder (Complete address and Phone no.)

(Er. Vishal Bagotra)  
Executive Engineer

CC: Guard File  
Notice Board





जम्मू केंद्राय विरवावद्यालय  
Central University of Jammu

राया-सूचानी (बागला), जिला सांबा-181143, जम्मू (जम्मू एवं कश्मीर)  
Rahya-Suchani (Bagla), District: Samba - 181143, Jammu (J&K)

BOQ for construction of sink & washbasin platform near canteen at CUJ campus.

S No	Description	Unit	Quantity	Rate(Rs)	Amount(Rs)
1	DSR 2.1.1 Earth work in surface excavation not exceeding 30 cm in depth but exceeding 1.5 m in width as well as 10 sqm in plan including getting out and disposal of excavated earth upto 50 m and lift upto 1.5 m. In All kinds of Soil	sqm	2.5	92.55	231.38
2	DSR 4.1.8 Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering 1:4:8 (1 cement: 4 coarse sand (Zone -III): 8 grade stone aggregate 40mm nominal size).	cum	0.5	5789.6	2894.8
3	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : DSR 6.4.1 Cement mortar 1:4 (1 cement : 4 coarse sand)	cum	0.25	7809.25	1952.31
4	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level.				
	DSR 6.13.1 Cement mortar 1:3 (1 cement: 3 coarse sand)	sqm	3.5	956.6	3348.1
5	DSR 4.2.3 Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to floor five: 1:2:4	cum	0.2	8554.5	1710.9
6	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and all complete above plinth level				
	DSR 5.22A.1 Mild steel and Medium Tensile steel bars	kg	15	82.1	1231.5

BR





जम्मू केंद्राय विरवावद्यालय  
Central University of Jammu

राया-सूचानी (बागला), जिला सांबा-181143, जम्मू (जम्मू एवं कश्मीर)  
Rahya-Suchani (Bagla), District: Samba - 181143, Jammu (J&K)

7	Providing and fixing 18 mm thick gang saw cut, mirror polished, pre moulded and pre polished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement: 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing to edges to give high gloss finish etc. complete in all respects. 8.2.1 Raj Nagar White Marble/Udaipur Green Marble/Zebra Black Marble				
	DSR 8.2.1 Area of slab over 0.50 sqm	sqm	1.8	2552.65	4594.77
8	DSR 8.5 Extra for providing opening of required size & shape for wash basin/ kitchen sink in kitchen platform, vanity counter and similar location in marble/ Granite/ stonework, including necessary holes for pillar taps etc. including moulding, rubbing and polishing of cut edges etc. complete.	each	3	734.55	2203.65
9	Providing and fixing Stainless Steel A ISI 304 (18/8) kitchen sink as per IS:13983 with C.I. brackets and stainless steel plug 40 mm, including painting of fittings and brackets, cutting and making good the walls wherever required :	each	1	5155.95	5155.95
	DSR 17.10.1.1 kitchen sink with drain board 510x1040 mm bowl depth 250 mm				
10	17.10.2.1 Providing & Fixing Kitchen sink without drain board 610X510X200 mm depth	each	1	3631.55	3631.55
11	Stone tile (polished) work for wall lining over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and cement slurry @ 3.3 kg/sqm including pointing in white complete.	sqm	1.8	2515.4	4527.72
	DSR 8.9.1.1 8 mm thick Raj nagar plain white marble/ Udaipur green marble/ Zebra black marble				
12	DSR 17.28.1.2 Providing & Fixing semi rigid PVC waste pipe for sink or wash basin including waste fittings complete	each	3	101	303







जम्मू केंद्राय विरवावद्यालय  
Central University of Jammu

राया-सूचानी (बागला), जिला सांबा-181143, जम्मू (जम्मू एवं कश्मीर)  
Rahya-Suchani (Bagla), District: Samba - 181143, Jammu (J&K)

13	Providing & fixing Stainless steel waste coupling of of 38 mm dia for fixing in sink and Wash basin(Market Rate). Heavy duty	each	3	300.00	900
14	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillartaps, 32 mm C.P. brass waste of standard pattern, including painting of fittingsand brackets, cutting and making good the walls wherever require:				
	White vitreous china wash basin 550X400 counter sunk with a single CP brass 15 mm pillar tap	each	1	3500.00	3500
15	DSR 13.1.1 12 mm cement plaster on faces of brick wall and RCC walls including hacking of the surfaces of mix 1:4( 1 cement:4 fine sand)	sqm	4.2	266.85	1120.77
16	DSR 13.41.1 Distempering with oil bound washable distemper of approved and manufacture to give an even shade New work (two or more coats) over and including water thin able priming coat with cement primer.	sqm	4.2	153.45	644
17	Providing and fixing square-mouth S.W. gully trap class SP-1 complete with C.I. grating brick masonry chamber with water tight C.I. cover with frame of 300 x300 mm size (inside) the weight of cover to be not less than 4.50 kg and Frame to be not less than 2.70 kg as per standard design: 100X100 mm size P type	each	1	2307	2,307
	19.4.1.1 With common burnt clay F.P.S. (non modular) bricks of class designation 7.5				
18	DSR 18.7.2 Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction. 20 mm nominal outer dia pipes. Makes ASTRAL PRINCE JINDAL AKJ SUPREME	rm	8	306.95	2,456

B/w





जम्मू केंद्राय विरवावद्यालय  
Central University of Jammu

राया-सूचानी (बागला), जिला सांबा-181143, जम्मू (जम्मू एवं कश्मीर)  
Rahya-Suchani (Bagla), District: Samba - 181143, Jammu (J&K)

19	Providing and fixing CP Brass swan neck table deck mounted sink tap 360 Rotating type Make Grohe, Somany, Jaguar, Parry Ware, CERA, hindware. Make and Model as decided by Engineer In Charge.	each	1	2000	2,000
20	DSR18.53.1 Providing & Fixing CP brass angle valve 15 mm nominal bore	each	3	535	1,605
21	DSR 18.74.2 providing and fixing un plasticised P.V.C. connection pipe with PTMT Nuts, collar and bush of approved quality and colour. 15 mm nominal bore with 45 cm length	each	3	112.5	338
22	Providing and fixing square-mouth S.W. gully trap class SP-1 complete with C.I. grating brick masonry chamber with water tight C.I. cover with frame of 300 x300 mm size (inside) the weight of cover to be not less than 4.50 kg and Frame to be not less than 2.70 kg as per standard design: 100X100 mm size P type	each	1	2307	2,307
	19.4.1.1 With common burnt clay F.P.S. (non modular) bricks of class designation 7.5				
23	Excavating trenches of required width for pipes, cables, etc including excavation for sockets, and dressing of sides, ramming of bottoms, depth upto 1.5 m, including getting out the excavated soil, and then returning the soil as required, in layers not exceeding 20 cm in depth, including consolidating each deposited layer by ramming, watering, etc. and disposing of surplus excavated soil as directed, within a lead of 50 m :				
	DSR 2.10.1.2 Pipes, cables etc. exceeding 80 mm dia. but not exceeding 300 mm dia	m	17	364.2	6,191

16/1




जम्मू केंद्राय विरवावद्यालय  
Central University of Jammu

राया-सूचानी (बागला), जिला सांबा-181143, जम्मू (जम्मू एवं कश्मीर)  
Rahya-Suchani (Bagla), District: Samba - 181143, Jammu (J&K)

Name of Work: Construction of sink & washbasin platform near canteen at CUJ campus.

Quotation Form

Estimated Cost (Inclusive of GST)	Quote Percentage(Above/At Par/Below)	
	In figures	In words
Rs.63960.00(Sixty three thousand nine hundred and sixty only)		

  
VISHAL SHARMA  
EE





जम्मू केंद्राय विरवावद्यालय

## Central University of Jammu

राया-सूचानी (बागला), जिला सांबा-181143, जम्मू (जम्मू एवं कश्मीर)  
Rahya-Suchani (Bagla), District: Samba - 181143, Jammu (J&K)

24	Supplying, fitting & fixing UPVC pipes and fittings conforming to I.S. 13592-1992 TYPE B with all necessary clamps, nails etc. including making holes in the walls, floor etc. and cutting trenches etc. in any floor through masonry/ concrete, mending good damages including vents and jointing & jointing materials (solvent/adhesive as per manufacture specification) complete. The rate should include fittings like single branch equal, double branch equal bend with door offsets, shoe head, tees, Ptrap, Strap or Qtrap, vent cowls as required etc. and similar specials as required for smooth commissioning of system as per direction of Engineer-Incharge. Rate to include fixing of pipe with walls with PVC clamps at every 1.5 m interval. For Soil pipe and sewerage system 110 mm dia.	m	17	518	8,806
<b>Total amount (A)</b>					<b>63,960</b>

Approved makes

UPVC PIPES & FITTINGS	SUPREME, FINOLEX, PRINCE KISAN, DIPLAST, ASTRAL, AKG
CPVC PIPES & FITTINGS	SUPREME, ASTRAL, PRINCE, JINDAL, AKG
CP FITTINGS	CERA, JAQUAR, HINDWARE
SANITARY WARE / FIXTURES / FITTINGS	JAQUAR, HINDWARE, PARRY WARE, CERA
VITRIFIED TILES & CERAMIC TILES	SOMANY, KAJARIA,