



जम्मू केंद्रीय विश्वविद्यालय  
Central University of Jammu

राया-सूचानी (बागला), जिला सांबा-181143, जम्मू (जम्मू एवं कश्मीर)  
Rahya-Suchani (Bagla), District: Samba - 181143, Jammu (J&K)

No: CUJ/W/2022/3088

Date: 30.03.2022

Sub: - Quotation.

Name of Work: Providing & Fixing of False tiles in already fitted grid system in the Office block of 0.00 level I of DDE building at Central University of Jammu, Rahya Suchani, Bagla.

Dear Sir,

CUJ invites quotation for providing and Installation of False ceiling tiles in the Office block of DDE building. The work includes removing the old tiles from the false ceiling grid system, stacking them properly at a place designated by University and fixing the new tiles in the false ceiling grid system. You are requested to quote the overall percentage for complete work: "At Par", or "Above" or "Below" in figures, as well as, in words (including GST) of the enclosed format. In case of any discrepancy noticed in the quoted percentage, the percentage quoted in words shall be considered. Electricity charges @ 1% shall be deducted in case the vendor uses the electricity from CUJ resources.

Terms and Conditions:-

1. The completion period is 7 days (Seven days) from the date of issue of work order.
2. The Estimated cost of work is Rs91300.00
3. Last date of submission of Quotation is 12/04/2022 at 12:00 hrs
4. Date of Opening of Quotation is 12/04/2022 at 15:00 hrs or as decided by Convenor LPC.
5. Validity of Quotation is 45 days from the date of opening of Quotation.
6. Bidders quoting percentage item wise shall be summarily rejected. Rates are inclusive of all taxes, loading Unloading, transportation Octroi, cess, GST etc. Rates are FOR at site.
7. Statutory deductions like TDS & Labour cess as per applicable rates will be made from the contractor's bill.
8. Rates quoted shall be firm and fix and no escalation shall be provided throughout the currency of the period of work.
9. No advance payment will be made.
10. GST Bill should be provided.
11. CUJ reserves the right to cancel the work before the commencement of work or at any stage of execution if found substandard or not as per required specifications.




जम्मू केंद्रीय विश्वविद्यालय  
Central University of Jammu

राया-सूचानी (बागला), जिला सांबा-181143, जम्मू (जम्मू एवं कश्मीर)  
Rahya-Suchani (Bagla), District: Samba - 181143, Jammu (J&K)

12. Payment shall be made through RTGS/NEFT
13. Work is to be executed as per CPWD Specification 2019 VOL-1&VOL-2 with up-to-date correction slip
14. If the bidder withdraws from the work after coming out as Lowest within the bid validity period, the bidder shall be debarred from applying for further works in the University for period of two year.
15. Bidders are required to submit following document along with Quotation:
  - i. Covering letter in Company letter head format.
  - ii. GST Registration/ Pan Card/Aadhar Card
  - iii. Contact Information of bidder (Complete address and Phone no.)

Encl: As Above

  
(Er. Vishal Bagotra)  
Executive Engineer

CC: Guard File  
Notice Board





# जम्मू केंद्रीय विश्वविद्यालय Central University of Jammu

राया-सूचानी (बागला), जिला सांबा-181143, जम्मू (जम्मू एवं कश्मीर)  
Rahya-Suchani (Bagla), District: Samba - 181143, Jammu (J&K)

Annexure-1

Sno	Description	Unit	Qty	Rate(Rs)	Amount(Rs)
1	Providing and fixing mineral fibre false ceiling tiles in existing frame work of T-grid of at all heights of size 595X595mm of approved texture, design and pattern. The tiles should have Humidity Resistance (RH) of 99%, Light Reflectance 85%, Thermal Conductivity k = 0.052 - 0.057 w/m K, Fire Performance as per (BS 476 pt - 6 &7) including levelling straightening of the existing grid structure . With 16 mm thick bevelled regular/mineral fibre false ceiling (NRC 0.55 to 0.6)	sqm	60	1335	80100
2	Providing and fixing in already fixed grid framework, 15 mm thick tegular/butt edged integral densified calcium silicate reinforced with fibre and natural filler false ceiling tiles of Size 595x595mm of approved texture, design and patterns as per CPWD Specification 2019, without perforation plain/designer light weight calcium silicate Anti-Microbial Bio-Safe coated false ceiling tiles Confirming to JIS-Z2801 and ASTM G-21. Rate to include levelling & Straighting of existing grid structure.	sqm	10	1120	11200
	<b>Total</b>				<b>91300</b>

*(Handwritten signature)*



जम्मू केंद्रीय विश्वविद्यालय  
Central University of Jammu

राया-सूचानी (बागला), जिला सांबा-181143, जम्मू (जम्मू एवं कश्मीर)  
Rahya-Suchani (Bagla), District: Samba - 181143, Jammu (J&K)

Quotation Form

Name of Work: Providing & Fixing of False tiles in already fitted grid system in the Office block of 0.00 level I of DDE building at Central University of Jammu, Rahya Suchani, Bagla.

Estimated Cost: Rs91300/-

Estimated Cost (Inclusive of GST)	Quote Percentage(Above/At Par/Below)	
	In figures	In words
Providing & Fixing of False tiles in already fitted grid system in the Office block of 0.00 level I of DDE building at Central University of Jammu, Rahya Suchani, Bagla.		

Signature & Stamp of the vendor